

PROPOSED SECTION AND SIDE ELEVATION 1:50





SPECIFICATION:

CONCRETE STRIP MIN. 600 x 300min. THICK TO CAVITY WALLS & MIN. 450 x 200 THICK TO 1/2 BRICK / LOADBEARING WALLS TO SITE SPECIFIC ENGINEERS DETAILS OR 425 WIDE CONCRETE TRENCH FILL FINISHED AT LEAST 150 BELOW G.L IN CLAY SOIL NOT AFFECTED BY TREE GROWTH OR REMOVAL. DEPTH OF FOUNDATIONS TO SUIT GROUND CONDITIONS TO FIRM BED & TO APPROVAL OF BUILDING INSPECTOR. N.B. PRECAUTION AGAINST ROOT DAMAGE TO BE AGREED ON SITE WITH BUILDING INSPECTOR AND TO NHBC STANDARDS — CHAPTER 4.2.

100 POWERFLOAT FINISH TO CONCRETE ON 75 XTRATHERM XT / UF INSULATION ON 300 um 1200g POLYTHENE DPM ON 150 MIN GROUND BEARING SLAB. N.B WHERE HARDCORE FILL EXCEEDS 600. FLOOR SLAB TO BE SUSPENDED & REINFORCED TO NHBC STANDARDS — CHAPTER 4.5. JUNCTIONS WITH LOADBEARING WALLS & EXTERNAL WALLS TO BE CONSTRUCTED AS TO PREVENT "COLD BRIDGING".

COLD WATER SERVICE PIPES TO BE INSULATED THROUGHOUT LENGTH IN SUBFLOOR WITH FOAMED PLASTIC MIN THICKNESS 25mm FOR 15 DIA PIPE & 19mm FOR 22 – 28mm DIA PIPE. WALL INSULATION (MIN. THERMAL RESISTANCE OF 0.6 M² K/W) BUILT IN BEHIND RECESSED METER BOXES. ELECTRICAL INSTALLATIONS TO BE IN ACCORDANCE WITH BS.7671. W.E INDICATES WATER ENTRY POINT.

ASTOS OR EQUAL CONTINUOUS DPC MIN. 150mm ABOVE F.G.L WITH D.P.M. UNDER GROUND FLOOR. CAVITIES FILLED WITH WEAK MIX CONCRETE TO WITHIN 225mm OF F.G.F.L.

302mm CAVITY CONSTRUCTION WITH WALL TIES TO BS.1243:1978 @ 750c/c HORIZONTALLY & 450c/c VERTICALLY & 450c/

1 No SELF CONTAINED MAINS OPERATED SMOKE ALARM TO BS.5446:PART 1. TO BE INSTALLED AT ENTRY / EXIT INDICATED THUS:— SD INTERCONNECTED & WIRED TO A SEPARATELY FUSED CIRCUIT WITH A DEDICATED MONITORING DEVICE FOR MAINS FAILURE.

