SHRUB SCHEDULE

Nr	Plant Name	Abbrev	Height (cm)	Container	Density/m²
141	Berberis candidula 'Amstelveen'	Berb cAm	20-30cm	3L	4.00
25	Bergenia cordifolia 'Purpurea'	Berg cP		9cm	5.00
22	Chaenomeles superba 'Jet Trail'	Chae JT	30-40cm	3L	3.00
29	Choisya ternata 'Sundance'	Chois tS	30-40cm	3L	3.00
67	Cornus sanguinea	Corn san	40-60cm	BR	3.00
22	Corylus avellana	Cory av	50-60cm	BR	2.00
21	Cytisus kewensis	Cyt xkew	40-60cm	2L	5.00
24	Elaeagnus ebbingei	El xebb	40-60cm	3L	2.00
14	Euonymus fortunei 'Silver Queen'	Euon fSQ	20-30cm	2L	6.00
47	Euphorbia characias wulfenii	Eupa wul		9cm	5.00
24	Hebe albicans 'Red Edge'	Heb RE	20-30cm	3L	4.00
62	Hebe pinguifolia 'Sutherlandii'	Heb Sut	20-30cm	2L	4.00
80	Hedera helix	Hed hel	40-60cm	2L	5.00
4	Hemerocallis 'Golden Chimes'	Hem GC		9cm	5.00
30	Heuchera micrantha 'Palace Purple'	Heu PPur		9cm	5.00
69	Hypericum moserianum	Hyp mos	30-40cm	3L	4.00
41	Ilex aquifolium	Ilx aq	30-40cm	3L	2.00
113	Lavandula angustifolia 'Munstead'	Lav Mun	20-30cm	3L	5.00
133	Lonicera nitida 'Silver Beauty'	Lon SB	20-40cm	3L	4.00
13	Perovskia atriplicifolia 'Blue Spire'	Pero BS		9cm	5.00
57	Rosa rugosa 'Alba'	Ros Alba	40-60cm	BR	4.00
27	Sedum spectabile 'Brilliant'	Sed Bri		9cm	5.00
40	Skimmia japonica 'Rubella'	Skim Rub	30-40cm	3L	4.00
90	Spiraea bumalda 'Goldflame'	Sp GF	30-40cm	3L	4.00
11	Thymus citriodorus 'Aureus'	Thym Aur		9cm	5.00
100	Vinca minor 'Alba'	Vin Alb	20-25cm	2L	5.00

TREE SCHEDULE

SPECIES		NoS REQD
	Ht in m	2.75-3.0
	Girth in cm	8-10
Malus sylvestris (Ms)		1
Sorbus aria (Sa)		3
Sorbus aucuparia 'Joseph's rock' (Sj)		4

Foundation design of new buildings shall accommodate proposed tree planting in accordance with NHBC guidelines.

HEDGE SCHEDULE

%age	Nr	Plant Name	Ht (cm)	Form/root
25.00	37	Crataegus monogyna	40-60cm	Transplant 1+1/BR
60.00	88	Fagus sylvatica	60-80cm	Transplant 1+1/BR
10.00	14	Prunus spinosa	40-60cm	BR
5.00	10	Rosa canina	30-40cm	BR

Planted in double staggered row, 450mm apart at 450mm centres (5/lin m).

BULB SCHEDULE

NR	SPECIES	PLANTING DENSITY	PLANTING DEPTH
35 Nr	wild daffodil	6-12/m²	5-8cm
35 Nr	snowdrop	8-16/m²	2.5-5cm

Wildflower bulbs planted at 6-12 plants per m² over approx half of the areas identified. Planted in single species drifts of 10-20 bulbs.

N

RECEIVED
21 JAN 2011

LOADING BAY

24Nr Elaeagnus ebbingei
80Nr Hedera helix
+35nr wild daffodil bulbs
35 nr snowdrop bulbs

Area under T5 retained at exisitng level, beyond retaining wall.

T5

T6

Proposed timber retaining wall. Horizontal boards fixed to timber posts set at 1.2m centres. To minimise damage to tree roots. Wall varies from 500mm to 1m high.

158.7
159
159.1
160

Paving amended to tarmac

12Nr Hypericum moserianum
22Nr Lonicera nitida 'Silver Beauty'

Existing grass area retained and extended.

12Nr Berberis candidula 'Amstelveen'
27Nr Berb cAm
11Nr Lon SB

Beech-hawthorn Hedge (5.00/m)
17Nr Crataegus monogyna
40Nr Fagus sylvatica
6Nr Prunus spinosa
5Nr Rosa canina

62Nr Berberis candidula 'Amstelveen'
Sa
39Nr Euphorbia characias wulfenii
Sa

T7

57Nr Rosa rugosa 'Alba'
40Nr Skimmia japonica 'Rubella'

14Nr Berb cAm
62Nr Hebe pinguifolia 'Sutherlandii'
9Nr Sedum spectabile 'Brilliant'
11Nr Thym Aur
8Nr Eupa wul
13Nr Perovskia atriplicifolia 'Blue Spire'
4Nr Hem GC

T3

T2

29Nr Choisya ternata 'Sundance'
21Nr Cytisus kewensis
30Nr Heuchera micrantha 'Palace Purple'
8Nr Sedum spectabile 'Brilliant'

Ivy growing over wall

Bench added
Planting amended to suit

14Nr Lavandula angustifolia 'Munstead'

T1

57Nr Hyp mos
20Nr Sp GF
25Nr Bergenia cordifolia 'Purpurea'
7Nr Vin Alb

8Nr Sed Bri
Ms

30Nr Lav Mun

Maintenance added to building planting amended to suit

covered cycle shelter

Paving amended to tarmac

DISABLED PARKING
2 spaces

56Nr Spiraea bumalda 'Goldflame'

18Nr Vinca minor 'Alba'

Paving amended to tarmac

STAFF PARKING
6 spaces

69Nr Lav Mun
22Nr Chae JT
Sa
14Nr Hebe albicans 'Red Edge'
14Nr Spiraea bumalda 'Goldflame'

26Nr Berberis candidula 'Amstelveen'

Signage added
Planting amended to suit

PATIENT PARKING
14 spaces

14Nr Euon fSQ
56Nr Vinca minor 'Alba'

Paving amended to tarmac

82Nr Lonicera nitida 'Silver Beauty'

10Nr Hebe albicans 'Red Edge'
18Nr Lonicera nitida 'Silver Beauty'

Sj
21Nr Vinca minor 'Alba'
22Nr Corylus avellana

Sj
67Nr Cornus sanguinea

Sj
41Nr Ilex aquifolium

Existing beech hedge trimmed back

Beech-hawthorn Hedge (5.00/m)
20Nr Crataegus monogyna
48Nr Fagus sylvatica
8Nr Prunus spinosa
5Nr Rosa canina

APPROX NORTH

KEY

T2 — Existing trees to remain. For schedule numbers refer to Tree Report. Also refer to Tree Protection dwg for protective measures.

Ms — Proposed tree planting. See schedule for species.

Proposed shrub planting. See schedule.

Proposed beech-hawthorn hedging. See schedule.

Proposed grass seeding. Manor Oaks Farm Flowering Lawn Mix, (80% grasses:20% low growing wildflowers) to be sown at 5gm/m². To be cut 3 times per year only.

Existing stone wall 900mm ht.

Proposed vertical bar fencing 1.6m high.

Existing conc panel fencing 1.8m high.

Proposed bitmac surfacing.

Proposed concrete sett paving. Marshalls Tegula (ML) or similar approved. Colour: traditional, size 120x160x60 laid herringbone.

Proposed textured concrete flag paving. Marshalls Saxon or similar approved, colour natural, size 300x300 or 900x600 as appropriate to location and levels.

NOTES: Thickness of paving to be checked by design team and contractor for adequacy.

FOR PLANTING SPECIFICATION NOTES SEE DWG NO 2596/2

Rev D. 14.01.11 Paving updated
Rev C. 11.01.11 M&E Plant added.
Rev B. 10.01.11 Planting amended to take into account updated siteplan.
Rev A. 15.09.10 Planting amended to take into account neighbours comments.

ECUS
Endcliffe Holt
343 Fulwood Road
Sheffield S10 3BQ
Tel. (0114) 2666282
Fax. (0114) 2666343
www.ecusltd.co.uk

Job: Lambsgate surgery, Hadfield

Title: Landscape Details

Drawn by	Date	Scale	Drg. no.
CTF	Sept 10	1:200 @ A2	2596/1D