HPK/2012/0218

16 APR 2012

Existing buildings

372
To be confirmed by S.E.

4465

Dresser

603
To be confirmed by S.E.

Dotted line indicates lean too and two storey buildings to be demolished.

New extension: New steel portals, 6000mm grid.
New portal stanchions on foundations to be designed by structural engineer with bracing as required and additional steelwork to tie new extension to existing buildings.
Personnel and fire exit doors to be solid core painted doors fixed to steel frame.

Existing extension: Gable end to be stripped, existing insulated door to be carefully dismantled and retained for future use.

25940
Dimension to be confirmed on demolishion

9626

New Loading bay

New extension

6000 6000

9785

New Loading Bay: Approx depth 1200mm dimension to be confirmed with laod bearing structure & retaining walls. Allow for forming 2 no. access ways with concrete steps and metal balustrading and with solid core access door with coded access panel.
Loading bay access vai 2 no. 4000mm wide x 5000mm hign insulated doors externallly and 2 no. 4000mm x 3800mm high insulated doors internally.

6127

4000 4000

880 698

33000

A.Cooper Construction Illustrator 91 Castlewood Road, Kersal Vale, Salford M7 3QW Tel.: 07544 841 244	Client Primapost Ltd.	Job Title New Extension 1 Staden Park Staden Lane Business Park Staden Lane, Buxton SK 17 9 RZ	Drawing Title Extension plan	Scale 1:125 @ A3 Job No: M01203 · Drawing No: 06 · Rev: –