HPK/2006/0522

HIGH PEAK BOROUGH COUNCIL
GLOSSOP SITE
RECEIVED
28 JUN 2006
FILE REF.....
REPLY REQUIRED.....

ADJOINING BARN

WELSH SLATE

RE-INSTALL MISSING SPLAYED STONE MULLIONS, PATTERNS TO MATCH; RECLAIMED MATERIAL. FIT NEW WINDOW FRAMES

W.12

W.13

STONE SLATE

REPLACE BOARDED DOOR

D.1

W.1

W.2

W.3

REINSTALL MISSING STONE MULLION: PATTERN TO BE DETERMINED AFTER REMOVING EXISTING FRAMES; FIT NEW WINDOW FRAMES

North

WALLS:- EXTENSIONS ON NORTH SIDE ARE IN RANDOM SANDSTONE; ALL OTHER WALLS ARE CRUDELY COURSED

WELSH SLATE

W.15

W.16

W.4

W.5

REMOVE STONE INFILL AND FIT TALLER WINDOW

W.6

NEW WINDOW FRAME

wing

D.3

NEW DOORWAY

West

W.7

FORM WINDOW OPENING IN EXISTING DOORWAY

lean-to

east

west

D.2

South

WELSH SLATE

W.17

W.18

NEW WINDOW FRAME

W.8

W.9

REOPEN FORMER DOORWAY INSTALL NEW DOOR & FRAME

D.4

NEW CILL

INFILLED DOORWAY

LEVEL OF WINDOW SURROUND TO EQUAL THAT TO R.H.S. OF DOOR.

W.3

WELSH SLATE

W.19

W.20

PROJECTING STONE STRING MOULDING

D.2

FIT NEW DOOR

NEW STONE CILL

W.1

INFILLED DOORWAY

ADJOINING BARN

wing: east / west

GLASS PANE SET INTO SLATEWORK WITH LEAD SOAKERS, FRAMELESS, FLUSH WITH ROOF

W.14

This application relates to the work shown to D.2 and W.3 only.
Other work shown was previously approved.

James Thornely
Architect:
Chinley 750415:

Work at Marsh Hall, Chapel-en-le-Frith.

Dwg. Title: Proposed Elevations

Dwg. No: 0022/4

Scale: 1:50