



TYPE 6 DETAIL SECTION

W2 shown, W4 similar with no vent W4 similar with no vent similar with no vent, cat flap set in 22mm painted timber boarding

tflap set in painted nber panel

NOTES:

Opening sizes relate to existing internal opening dimensions. 15mm has been added to all vertical heights. Internal finishes not shown on details. All structural openings to be checked by manufacturer prior to manufacture.

Casement windows to have stormproof hinges, weatherseals (white), locking with night vent facility.

Detail generally to match existing window W10 previously approved by Conservation Officer.

All windows to be double glazed to achieve a minimum of 1.6W/m2k unless stated otherwise.

All windows to be hardwood (marante or similar hardwood from FSC source), primed in the factory. If full factory glazed allow finish of 3 coats microporus paint.

Bituminous felt dpc and mastic sealant to heads, jambs and cills of all external openings (min 150 girth) pinned forward to all window and door openings. Location of dpc on dwgs indicitive only - to be agreed on site once existing window / door removed.

Ensure all existing cills fall away from the window. Window to be set back min 75mm at jamb.

Toughened safety glazing to all glazing in windows below 800mm above finished floor level.

Detail to be advised by window manufacturer and agreed with Conservation Officer.

TYPE 3 - SLIDING SASH

TYPE 4 - FIXED SASH

TYPE 5 - CASEMENTS WITH 2 LIGHTS

TYPE 6 - SPECIALS TYPE 1 - FIXED LIGHT CASEMENT

TYPE 2 - FIXED AND OPENING CASEMENTS IN GROUPS OF 3 OR 5 WITH STONE MULLIONS BETWEEN WINDOW TYPES W3,W11,W17,W18,W19,W20 W7,W8,W9,W15(partial),W16 W5,W6,W15(partial) W12,W13,W14 W2, W4

Rev B: 08.08.12 Rev A: 12.06.12 W12 and W14 omitted, plan details added, type 6 included in 'window schedule sheet 1' Glazing bars added to W12 and W14, Type 5 false glazing bar detail added



HIGH PEAK ARCHITECTS

2nd Floor, Wharf House, Wharf Road, Whaley Bridge, High Peak, Derbys SK23 7AD
Tel: 01663 719717 Website: highpeakarch.com Email: hpa@highpeakarch.com

Marsh Hall Farm, Marsh Hall Lane Replacement windows and doors Window Schedule and details 1 1123.02

Scale: 1:10 & 1:2 detail @ A1 Date: May 2012 DO NOT SCALE OFF THIS DRAWING