John F. Lomas. M.R.I.C.S., M.B.Eng
Rothbury
Chapel Road
Hayfield
High Peak SK22 2JF
Tel. 01663 745186

HPK/2013/0124

drg no 13·3/4

HIGH PEAK
6 MAR 2013

landscaping plan

1:100

1·20m high close boarded timber fence. treated with dark stain / preservative

garden (lawn)

garden (lawn)

X

New steps formed in natural stone

black, mild steel railings to 1·10m above ground level

black, mild steel railings to 1·10m above ground level

New retaining wall with natural stone face to match existing

existing natural stone retaining wall

up

up

Natural stone wall

Remove existing retaining wall

paved area

paved area

Fence detail as to rear garden

Paved area formed in natural stone pavings, with fall to surface water gully

excavate site as necessary

Fence detail as to rear garden

Fence detail as to rear garden.

X

2no carparking spaces formed in block paving, with sand infill at joints, providing a permeable surface

2no carparking spaces formed in block paving, with sand infill at joints, providing a permeable surface

end of fence, in line with house

end of fence, in line with house

shrubs

ramp

shrubs

shrubs

ramp

shrubs

New access to highway to Highway Authority specification

New access to highway to Highway Authority Specification.

Ramps formed in natural stone pavings

New 1·80m wide footway to frontage

600mm high natural stone wall with natural stone capping

1·35m wide footway to frontage of no 36