

- EXTERNAL WORKS:

 DEEP CLEAN ALL EXTERNAL WALL SURFACES AND REMOVE ANY GRAFFITI

 REPAIR DAMAGED WALLS AND STONEWORK IF REQUIRED


 TREATMENT TO BE TAKEN UP TO FIRST FLOOR ONLY. ANY PROPOSALS ABOVE FIRST FLOOR TO BE REFERRED BACK TO THE CWG.

 DOOR: TIMBER FINISH: RUB DOWN AND RE-VARNISH RETAIN EXISTING HANDRAILS AND DEEP CLEAN CLEAN GLAZING INTERNALLY AND EXTERNALLY BETWEEN SECONDARY GLAZING.

 WINDOW FRAMES: TIMBER FINISH: RUB DOWN AND RE-VARNISH

- WINDOW FRAMES: TIMBER FINISH: RUB DOWN AND RE-VARNISH WINDOW: REMOVE VINYL FROM 6NO WINDOWS WINDOW: REPLACE ONE FROSTED GLAZED PANEL CLEAN, REPAIR AND RE-LAMP LIGHTING CLEAN VENTS CLEAN EXISTING LETTERBOX ON FRONT DOOR REMOVE ALL UNSIGHTLY WEEDS

- SIGNAGE/MERCHANDISING:
 REMOVE EXISTING FASCIA SIGNAGE
 MAKE GOOD TO FASCIA AND INSTALL 2NO NON ILLUMINATED 376MM HIGH INDIVIDUAL LETTERS WITH WHITE FACES AND BULEBERRY RETURNS
 REMOVE EXISTING PROJECTION SIGN
 INSTALL NEW 750MM EXTERNALLY ILLUMINATED PROJECTION SIGN
 INSTALL NEW LETTERBOX SIGNAGE
 INSTALL NEW LETTERBOX SIGNAGE
 INSTALL NEW SOLAR FILM TO SOUTH FACING WINDOWS (CONTRACTOR TO CONFIRM)
 INSTALL NEW WELCOME SIGN
 INSTALL 1NO A0 POSTER UNITS
 INSTALL BLUEBERRY GRADIENT SECURE VINYL TO 1NO WINDOW



SIDE ELEVATION OF PROJECTING SIGN

rev, d	ate .	details	by	I nev.	date	details	by	I notes				1
P1 0		MERCHANDISING UPDATED	KR					-	PROPOSED LAYOUT IS SUBJECT TO	ro:		NW Buxton
P2 1-	0.08.13	SIDE ELEVATION OF PROJECTING SIGN ADDED. UPDATED FOR PLANNER	MJM KR						LANDLORDS CONSENT	NO		2 Spring Gardens, Buxton
P4 2	6.09.13	SIGNAGE CHANGED AFTER PLANNER COMMNTS	KR						(TENURE: FREEHOLD)			SK17 6DG
									PLANNING CONSENT	YES		
									LISTED BUILDING CONSENT	NO		
				1					ADVERTISEMENT CONSENT	YES		

Drawing to be read in conjunction with Contractors Scope of Works.

drawing number	revision	drawing title	scale	1:50
HBR22 AR(99)014	P4	Scoping Drawing	date	31.05.13
		Proposed	drawn	KR
status Information		SIDE ELEVATION	format	A1