HPK 2013 0696

C.D.M. Regulations 1994:
These drawings have been produced for the purpose of applying for Planning and Building Regulations only. If the project progresses on to site without the involvement of Inside Out Design, the Client and Contractor must ensure that they fulfil their duties in respect of the Construction, (Design and Management) Regulations 1994.
If advice is required, please do not hesitate to contact Inside Out Design.

EXTG F.F.L. - 100.030
PROP F.F.L. - 100.130

EXTG F.F.L. - 100.030
PROP F.F.L. - 100.130

F.F.L. - 99.900

F.F.L. - 99.900

F.F.L. - 99.900

F.F.L. - 99.900

UNIT 1

UNIT 2

UNIT 3
(SPEC)

UNIT 4
(SPEC)

EXISTING BUILDING TO
RECEIVE NEW ROOF

WOOLLEY BRIDGE ROAD

ACCESS ROAD

P.V.C. STRIP CURTAIN

LOADING DOCK

SUPPORT TO FLOOR EDGE OVER TO STRUCTURAL ENGINEERS DETAILS

SIDE ACCESS ROAD ELEVATION.

SIDE ACCESS ROAD ELEVATION, CONT.

EXTENT OF ELEVATION CONSTRUCTED FROM RECLAIMED STONE

EXTENT OF ELEVATION TO BE CONSTRUCTED FROM EXTERNAL QUALITY COLOURED FAIR FACED BLOCKWORK

BUILDING AREA
4,761 m²

REV	DATE	BY	CH	AP	COMMENTS
A	07.02.01				GEN AMENDMENTS TO CLIENTS INSTRUCTIONS
B	15.02.01				AMENDMENTS TO GABLE RIVERSIDE ELEVATION
C	20.03.01				NOTES ADDED
D	02.07.01				LOADING DOCKS ADDED & ELEVS AMENDED
E	06.07.01				LOADING DOCK SIZES AMENDED
F	12.10.01	RM			NOTES OMITTED AND PHASING INDICATED
G	06.11.01	RM			ROOF JUNC BETWEEN PHASE 1 & 2 AMENDED
H	11.02.02	RM			WINDOWS ADDED TO GABLE ELEVATION
J	17.05.02	RM			OFFICE LAYOUTS ADDED, WINDOWS REMOVED FROM GABLE & FRONT ELEVATION AMENDED
K	22.05.02	RS			AMENDMENTS TO CLIENTS INSTRUCTION
L	12.08.02	MS			PLAN DIMS ADDED, STAIRCASES AMENDED, ELEVATION AMENDED TO BLOCK DIMS.
M	23.08.02	AM			AMENDMENTS TO ELEVATION AND STANCHION SIZES ON GRIDLINE 3-A & 3-B
N	19.09.02	RM			PEDESTRIAN DOOR INTO THE LOADING DOCK REPOSITIONED & REAR ELEVATION REDESIGNED
P	30.09.02	AM			AMENDMENTS TO DOOR OPENINGS AND STAIRCASE ENCLOSURES
Q	27.11.02	RM			AMENDED POSITION OF UNIT 12 ESCAPE DOOR & REAR YARD GATE OMITTED
R	25.04.03	AM			AS BUILT INFORMATION ADDED.

PROJECT
ETHEROW INDUSTRIAL PARK
WOOLLEY BRIDGE
GLOSSOP

TAMESIDE M BOROUGH COUNCIL
POST ROOM
RECD 29 JAN 2014

CLIENT
REALTY ESTATES

EXISTING + PROPOSED PLAN AND ELEVATIONS

DRAWING NR
2001.01.04.003

DATE	REVISION	SCALE
JAN 2001	R	1:200
DRAWN BY	CHECKED	APPROVED
RM		

INSIDE OUT DESIGN ASSOCIATES LIMITED
CHARTERED ARCHITECTS & DESIGN CONSULTANTS
RIBA
The Old Bank 358 Manchester Road Hollinwood Oldham Lancashire OL8 3HJ
telephone 0161 627 3555
facsimilie 0161 627 3553
e-mail design@insideoutdesign.co.uk
website www.insideoutdesign.co.uk

THYSSEN SCHACHTBAU GROUP

DO NOT SCALE FROM THIS DRAWING
COPYRIGHT INSIDE OUT DESIGN ASSOCIATES LIMITED