



French drain discharge from septic tank as per NWWA requirements. First leg from tank to be perforated land drain in hardcore surround. Second leg to be hardcore soakaway only. Third leg as first with overflow discharge to watercourse.

Line of new boundary fence.

Conder or similar approved grp septic tank installation. Size 3000l.

100mm foul sewer connection.

NEWBROOK HOUSE
COMBS

Scale 1:200

Site Plan