

PROPOSED ROOF STRUCTURE 1:50
FORMER WHITE LION

REVISIONS:
THE FORMER WHITE LION
HOLKER ROAD
BUXTON

SCALE: 1:50
DATE: MARCH'17/DRAWN: AJS

CHECKED: AJS

©THIS DRAWING AND THE BUILDING WORKS DEPICTED ARE THE COPYRIGHT OF AJS ARCHITECTURE
AND MAY NOT BE REPRODUCED OR AMENDED EXCEPT BY WRITTEN PERMISSION. NO LIABILITY WILL BE ACCEPTED
FOR AMENDMENTS MADE BY OTHER PERSONS.

A.J.S ARCHITECTURE



32 carr road,
buxton,
derbyshire,
sk17 6wf.

h: 01298 26062
m: 07794 400237

DRAWING No: PROPOSED 06A

B REGS COMPLIANT

0M 1M 2M 3M



ALL EXISTING CENTRAL VALLEYS ARE IN EXTERNELY POOR
CONDITION AND REQUIRE REPLACEMENT WHEN THE EXISTING
ROOF COVERINGS ARE REMOVED AS PART OF THE REQUIRED
WORKS. MOST ROOF TIMBERS LOOK RETAINABLE. HOWEVER ALLOW
FOR 25% PC SUM REPLACEMENT TO MATCH VALLEYS TO 100mm
KINSPAN BOARD ONTO 19mm MARINE GRADE EXTERNAL
PLYBOARD WITH 2000g DPM. FINISH OVER TO BE PLYBOARD WITH
VAPOUR MEMBRANE AND CODE 5 LEAD DRESSED MIN 450mm TO
ROOF SLOPE.

ALL CEILING LINES ARE TO FOLLOW THE RAFTER SLOPE WITH
60mm SUPERQUILT BETWEEN AND BELOW TO TAKE PBD AND
SKIM FINISH. RETAIN ALL EXISTING EXPOSED PURLIN AND TRUSS
WORK. MAKE GOOD AS REQUIRED. ALLOW FOR ALL TIMBER TO BE
TREATED AGAINST SURFACE SPREAD OF FLAME.

ALL EXISTING CENTRAL VALLEYS ARE IN EXTERNELY POOR
CONDITION AND REQUIRE REPLACEMENT WHEN THE EXISTING
ROOF COVERINGS ARE REMOVED AS PART OF THE REQUIRED
WORKS. MOST ROOF TIMBERS LOOK RETAINABLE. HOWEVER ALLOW
FOR 25% PC SUM REPLACEMENT TO MATCH VALLEYS TO 100mm
KINSPAN BOARD ONTO 19mm MARINE GRADE EXTERNAL
PLYBOARD WITH 2000g DPM. FINISH OVER TO BE PLYBOARD WITH
VAPOUR MEMBRANE AND CODE 5 LEAD DRESSED MIN 450mm TO
ROOF SLOPE.

ALL CEILING LINES ARE TO FOLLOW THE RAFTER SLOPE WITH
60mm SUPERQUILT BETWEEN AND BELOW TO TAKE PBD AND
SKIM FINISH. RETAIN ALL EXISTING EXPOSED PURLIN AND TRUSS
WORK. MAKE GOOD AS REQUIRED. ALLOW FOR ALL TIMBER TO BE
TREATED AGAINST SURFACE SPREAD OF FLAME.

ALLOW FOR BULKHEAD
TO STAIRS BELOW

ALLOW FOR ALL EXISTING TIMBER BOARDING
TO BE CAREFULLY REMOVED TO EXPOSE
RAFTERS. REMOVE EXISTING SLATES AND
ALLOW FOR NEW TYVEK MEMBRANE TO
BATTENS TO RE-LAY SLATE. INSULATE
BETWEEN AND BELOW RAFTER LINE WITH
60mm SUPERQUILT TO BE BOARDED OUT
AS ORIGINAL RETAINED FINISH IN
ACCORDANCE WITH LISTED REQUIREMENTS