- This drawing is the Copyright of Saville Landscape Design Ltd & cannot be reproduced in any form without the consent of the company.
- All dimensions shall be verified by the Contractor (s) on site prior to work commencing and relevant orders being placed.
- Any discrepancies are to be brought to the attention of the Contract Administrator for instruction prior to proceeding.

N

0 5 10 20m
1:200

KEY

- Existing tree or vegetation to be retained & protected in line with Arboriculturalist proposals
- Existing tree or vegetation to be removed in line with Arboriculturalist proposals
- Proposed Tree — Extra Heavy Standard Tree,14-16cm girth, set in soft landscaping with irrigation pipe & double stake support
- Proposed Tree (Rear gardens) — Feathered, 10-12cm girth, set in soft landscaping with irrigation pipe & single stake support
- Small ornamental tree — 2m high, set in soft landscaping
- Ornamental Hedge — 0.6-1.0m high hedge planted @ 2-4 per lin.m with 50mm ornamental bark mulch dressing
- Native hedge mix — Whips/ transplants/ container grown plants planted in double staggered rows (rows 500mm apart), 7 per lin. m with suitable spiral guards
- Ornamental shrub planting — Plants supplied in 3-5L pots planted @ 3 -6/m2 in 450mm imported topsoil with 50mm ornamental bark mulch dressing
- Feature specimen shrub — 10-30L containers planted in 600mm imported topsoil
- Grass — Grass Seed OR Turf laid on minimum 150mm imported topsoil
- Vehicular block paving — Tobermore Tegula, Bracken colour, 208x173mm, laid in a herringbone pattern with Charcoal colour blocks to delineate bays or similar approved
- Vehicular block paving — Tobermore Tegula, Slate colour, 208x173mm, laid in a herringbone pattern or similar approved
- Grassblock grass reinforcement surfacing
- Pedestrian Concrete flag paving — Tobermore Mayfair flag paving, 450x450x50mm, Silver colour, textured finish, chamfered edge, laid in a stack bond pattern or similar approved

All kerbs & edgings to be Tobermore Country Kerb or similar approved. All public footpaths & carriageways to be tarmac surfacing to High Peak Council Highways adoptable standards.

- Existing pallisade fence
- 2.1m high fence comprising 1.5m high close boarded panels, 0.3m high trellis, 0.3m concrete gravel board & concrete support posts — Hedgehog friendly gravel boards to be intermittenty installed on site boundary
- 1.8m high fence comprising 1.2m high close boarded panels,0.3m high trellis, 0.3 concrete gravel board & concrete support posts — Hedgehog friendly gravel boards to be intermittenty installed on site boundary
- 1.2m high fence comprising 0.9m close boarded panel, 0.3m concrete gravel board & concrete support posts
- 1.2m high metal estate railings
- 1.1m high metal vertical bar railings
- 0.90m high drystone wall to match existing boundary, materials on site to used in construction



TYPICAL BOUNDARY DETAIL ELEVATIONS Scale 1:50

2100mm high timber fence

1800mm high timber fence

1200mm high timber fence

1200mm high estate railings

All metalwork to be galvanised steel railings painted RAL 9005 colour

1100mm high railings

Drystone wall

Rev	Description	Initial	Date
C	West section of site amended to arc pops	KAS	June20
B	Amended to arc comments	KAS	April20
A	Amended to arc comments	KAS	Apr20

saville LANDSCAPE DESIGN
Hatherlow House Romiley Stockport Cheshire SK6 3DY
T : 0161 406 7333 M : 07502 269193
E : info@savillelandscape.co.uk W : www.savillelandscape.co.uk

CLIENT
Johnnie Johnson Housing

PROJECT TITLE
Buxton Rd, Chinley

DRAWING TITLE
Landscape GA

STATUS
PRELIMINARY

SCALE	SHEET SIZE	DRAWN	CHECKED	DATE
1:200	A0	KAS	-	June 20
PROJECT NO.		DRAWING NO.		REV.
257		01		C