Plant Schedule

QTY	UNIT	CODE	PLANT NAME	STOCK	SIZE	SPACING
Shrubs						
6	No.	Ame lam 25L	Amelanchier lamarckii	C 25L	150-180cm	1/m2

QTY	UNIT	CODE	PLANT NAME	STOCK	FORM	GIRTH/HEIGHT
Trees						
15	No.	ACE JEF hs	Acer x freemanii 'Jeffersed'	RB	STD	12-14cm
14	No.	ACE QUE hs	Acer platanoides "Emerald Queen"	RB	STD	12-14cm
18	No.	ALN GLU hs	Alnus glutinosa	RB	STD	12-14cm
42	No.	BET PEN hs12	Betula pendula	RB	STD	12-14cm
12	No.	CAR FRA hs	Carpinus betulus "Frans Fontaine"	RB	STD	12-14cm
12	No.	LIQ STY hs	Liquidambar styraciflua	RB	STD	12-14cm
6	No.	PRU SUN hs	Prunus 'Sunset Boulevard'	B	STD	12-14cm
10	No.	Pru pad hs	Prunus padus	RB	STD	12-14cm
9	No.	PRU SCH hs	Prunus x schmittii	RB	STD	12-14cm
13	No.	QUE ROB12	Quercus robur	RB	STD	12-14cm
9	No.	SAL CAP hs	Salix caprea	RB	STD	12-14cm
19	No.	SOR AUC hs	Sorbus aucuparia	RB	STD	12-14cm
9	No.	SOR JOS hs	Sorbus 'Joseph Rock'	RB	STD	12-14cm
18	No.	TIL STR hs	Tilia cordata "Streetwise"	RB	STD	12-14cm
11	No.	TIL COR hs	Tilia cordata	RB	STD	12-14cm

QTY	UNIT	CODE	PLANT NAME	STOCK	SIZE
Hedges					
	m	Beech Hedge	Fagus sylvatica	B Trans	60-80cm
	No.	Plants spaced @ 4/m in a Double Staggered Row			

PERCENT	QTY	UNIT	PLANT NAME	STOCK	SIZE
Plant Mixes					
ORNAMENTAL GROUNDCOVER MIX planted @ 6/m2					
20%		No.	Bergenia cordifolia	C 1L	Full pot
20%		No.	Galium odoratum	C 1L	Full pot
20%		No.	Geranium 'Johnson's Blue'	C 1L	Full pot
5%		No.	Heuchera 'Key Lime Pie'	C 1L	Full pot
20%		No.	Liriope muscari	C 1L	Full pot
10%		No.	Luzula nivea	C 1L	Full pot
5%		No.	Nepeta racemosa 'Walker's Low'	C 1L	Full pot
Individual varieties to be planted in groups of approximately 3 or 5.					
SUN SHRUB/HERB. MIX planted @ 3/m2					
20%		No.	Chaenomeles japonica	C 3L	40-60cm
10%		No.	Hebe 'Marjorie'	C 3L	30-40cm
10%		No.	Rudbeckia fulgida sullivantii 'Goldsturm'	C 3L	Full pot
10%		No.	Echinacea purpurea	C 3L	Full pot
10%		No.	Anemone x hybrida 'Honorine Jobert'	C 3L	Full pot
10%		No.	Lavandula angustifolia 'Hidcote'	C 3L	20-30cm
10%		No.	Potentilla fruticosa 'Abbotswood'	C 5L	30-40cm
20%		No.	Sarcococca humilis	C 3L	20-25cm
Individual varieties to be planted in groups of 3.					
Chaenomeles to be positioned furthest from pathways.					
SHADE SHRUB/HERB. MIX planted @ 3/m2					
20%		No.	Euonymus fortunei 'Emerald Gaiety'	C 3L	20-30cm
20%		No.	Tellima grandiflora	C 3L	Full pot
20%		No.	Hosta 'Tall Boy'	C 3L	Full pot
10%		No.	Mahonia aquifolium 'Apollo'	C 3L	20-30cm
20%		No.	Sarcococca humilis	C 3L	20-25cm
10%		No.	Viburnum davidii	C 3L	20-30cm
Individual varieties to be planted in groups of 3.					
NATIVE SHRUB MIX 6 planted @ 1m centres					
20%		No.	Corylus avellana	B Trans	60-80cm
20%		No.	Viburnum opulus	B Trans	60-80cm
15%		No.	Cornus sanguinea	B Trans	60-80cm
15%		No.	Prunus padus	B Trans	60-80cm
10%		No.	Crataegus monogyna	B Trans	60-80cm
10%		No.	Malus sylvestris	B Trans	60-80cm
10%		No.	Sambucus nigra	B Trans	60-80cm
Individual varieties to be planted in groups of approximately 3-7					
NATIVE UNDERSTORY SHRUB MIX planted @ 3/m2					
20%		No.	Viburnum opulus	B Trans	60-80cm
20%		No.	Sambucus nigra	B Trans	60-80cm
20%		No.	Cornus sanguinea	B Trans	60-80cm
20%		No.	Corylus avellana	B Trans	60-80cm
20%		No.	Ligustrum vulgare	C 3L	40-60cm
MEDIUM SEMI-NATIVE SHRUB MIX planted @ 4/m2					
5%		No.	Chaenomeles japonica	C 3L	40-60cm
5%		No.	Chaenomeles speciosa	C 3L	40-60cm
15%		No.	Hebe 'Midsummer Beauty'	C 3L	30-40cm
15%		No.	Skimmia japonica 'Rubella'	C 2L	30-40cm
10%		No.	Daphne laureola	C 3L	20-30cm
10%		No.	Hypericum androsaemum	C 3L	30-40cm
10%		No.	Salix repens	C 3L	40-60cm
10%		No.	Cornus sanguinea	B Trans	60-80cm
10%		No.	Rosa canina	B Trans	60-80cm
10%		No.	Ligustrum vulgare	B Trans	60-80cm
Individual varieties to be planted in groups of approximately 3-5.					
Chaenomeles and Rosa canina to be positioned furthest from pathways.					
GENERAL WILDFLOWER MEADOW MIX seeded @ 4g/m2					
100%		No.	No. EM2 Standard General Purpose Meadow Mixture	Seed	
Seeded at 4g m2 over prepared ground					
WET MEADOW MIX seeded @ 4g/m2					
100%		No.	No. Wet Wildflower Meadow Seed Mix	Seed	
Seeded at 4g m2 over prepared ground from Habitat Aid					
NATIVE REEDS MIX planted @ 3/m2					
15%		No.	Carex acutiformis	C 1L	
15%		No.	Iris pseudacorus	C 1L	
15%		No.	Sparganium erectum	C 1L	
15%		No.	Scirpoides holoschoenus	C 1L	
10%		No.	Juncus articulatus	C 1L	
10%		No.	Lythrum salicaria	C 1L	
10%		No.	Ranunculus lingua	C 1L	
5%		No.	Phragmites australis	C 1L	
5%		No.	Typha latifolia	C 1L	
Individual varieties to be planted in groups of approximately 5-7.					

Notes and Abbreviations

B	=	Bare root (bagged).
C	=	Container (or pot) grown, followed by size of the container (or pot).
FORM	=	Shape of tree as supplied by the nursery.
QTY	=	Quantity
RB	=	Rootballed (balled and wrapped).
SIZE	=	Height or Spread of juvenile plant.
Std	=	(clear stem) Standard.
STOCK	=	Root condition/protection method eg Bare root.
Trans	=	Transplant (or undercut seedling).

- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.



Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when comparedto the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

Soft Works

Existing Tree
To be retained.
Refer to arboricultural drawings.

Existing Tree
To be removed / pruned.
Refer to arboricultural drawings.

Existing Woodland
To be retained.
Refer to arboricultural drawings.

Existing Hedge
To be retained.
Refer to arboricultural drawings.

Proposed Tree Planting
Clear stem heavy standard tree.

Proposed Specimen Shrub Planting

Proposed Hedge Planting
To plot gardens.
704.6910 linear metres

Proposed Groundcover Planting
Ornamental planting mix. 36.1609 m²

Proposed Ornamental Shrub & Herbaceous Planting
Ornamental shrub and herbaceous perennials mix.
628.0421 m²

Proposed Semi-Native Shrub Planting
Ornamental and native shrub mix. 322.1839 m²

Proposed Native Shrub Planting
Native shrub mix. 1864.5031 m²

Proposed Woodland Understory Planting
Native mix. 1340.2220 m²

Proposed Turf Grass
To front gardens. 850.6609 m²

Proposed Seeded Grass
To rear gardens. 9466.5638 m²

Proposed Seeded Amenity Grass
To public areas. 1470.2202 m²

Proposed Seeded Species Rich Wildflower Meadow
To public areas. 12181.7394 m²

Proposed Wet Meadow
To pond area. 1142.6080 m²

Native Reeds Mix
To pond area. 32.2571 m²

Pond Water
Approx 117.6260 m²

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P03	05/04/23	UPDATED LAYOUT - SUB STATION	RS	SA
P02	21/03/23	UPDATED POND LAYOUT AND RED LINE BOUNDARY	RS	SA
P01	25/01/23	FIRST ISSUED	RS	SA

URBAN GREEN

A: Ground Floor, The Tower,
Deva City Office Park, Trinity Way,
Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk

Client: BARRATT HOMES

Project: HOGSHAW FARM, BUXTON

Title: SOFT LANDSCAPE PLAN 2/4

Issue: PLANNING

Drawn:	Checked:	Approved:
RS	SA	ME

Project:	Scale @ A0:	Date:
UG1795	1:250	25/01/23

Dwg No:	Revision:
UG_1795_LAN_SL_DRW_03	P03