

Node ID	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Width (mm)	Node Type	Manhole Type	Connections	Link ID	IL (m)	Dia (mm)	Link Type
F16	65.067	-34.751	163.872	1.394	450		Manhole	Plastic Inspection Chamber	1 0	1 1.005 0 1.006	162.478 162.478	100 100	Circular Circular
F7	80.412	-27.043	164.142	1.000	450		Manhole	Plastic Inspection Chamber	0	0 2.000	163.142	100	Circular
F8	75.726	-29.411	164.142	1.066	450		Manhole	Plastic Inspection Chamber	0 1	1 2.000 0 2.001	163.076 163.076	100 100	Circular Circular
F9	71.081	-31.752	164.142	1.131	450		Manhole	Plastic Inspection Chamber	0 1	1 2.001 0 2.002	163.011 163.011	100 100	Circular Circular
F15	60.533	-37.042	163.872	1.330	450		Manhole	Plastic Inspection Chamber	1 0	1 1.004 0 1.005	162.542 162.542	100 100	Circular Circular
F14	55.855	-39.396	163.872	1.264	450		Manhole	Plastic Inspection Chamber	1 0	1 1.003 0 1.004	162.608 162.608	100 100	Circular Circular
F13	49.145	-42.007	163.572	0.873	450		Manhole	Plastic Inspection Chamber	1 0	1 1.002 0 1.003	162.699 162.699	100 100	Circular Circular
F11	39.291	-45.914	163.572	0.740	450		Manhole	Plastic Inspection Chamber	1 0	1 1.000 0 1.001	162.832 162.832	100 100	Circular Circular
F12	44.125	-43.998	163.572	0.805	450		Manhole	Plastic Inspection Chamber	1 0	1 1.001 0 1.002	162.767 162.767	100 100	Circular Circular
F17	70.052	-34.138	164.142	1.727	450		Manhole	Plastic Inspection Chamber	1 2 0	1 1.006 2 2.002 0 1.007	162.415 162.415 162.415	100 100 100	Circular Circular Circular
F18	72.616	-39.224	164.380	2.036	1500		Manhole	Plastic Inspection Chamber	1 2	1 1.007 2 3.005	162.344 162.344	100 100	Circular Circular
F4	67.961	-50.698	164.700	1.058	450		Manhole	Plastic Inspection Chamber	1 0	1 3.002 0 3.003	163.642 163.642	100 100	Circular Circular
F3	64.002	-53.042	164.700	1.000	450		Manhole	Plastic Inspection Chamber	1 0	1 3.001 0 3.002	163.700 163.700	100 100	Circular Circular
F2	60.054	-55.382	165.000	1.059	450		Manhole	Plastic Inspection Chamber	1 0	1 3.000 0 3.001	163.941 163.941	100 100	Circular Circular
F1	56.002	-57.783	165.000	1.000	450		Manhole	Plastic Inspection Chamber	0	0 3.000	164.000	100	Circular
F10	32.585	-48.265	163.500	0.579	450		Manhole	Plastic Inspection Chamber	0	0 1.000	162.921	100	Circular
F5	70.891	-49.127	164.700	1.105	450		Manhole	Plastic Inspection Chamber	0 1	1 3.003 0 3.004	163.595 163.595	100 100	Circular Circular
F6	71.012	-44.598	164.400	1.100	450		Manhole	Plastic Inspection Chamber	0 1	1 3.004 0 3.005	163.350 163.300	100 100	Circular Circular

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER HBL DRAWINGS ISSUED FOR THIS PROJECT

P03	AUG23	ES	REVISED IN LINE WITH HYDRAULIC MODEL P07	ES	LM
P02	JUL23	ES	REVISED TO MATCH HYDRAULIC MODEL P06	AP	
P01	MAY23	ES	FIRST ISSUE	ES	
REV.	DATE	DRAWN	DESCRIPTION	CHKD	APPRD
STATUS DESCRIPTION				STATUS	
FOR INFORMATION				S2	

HBL

Brook House
Weybrook Road,
Manchester M19 2QD
+44 (0)161 432 9977 | www.hbl.ltd
Consulting Civil & Structural Engineers

PROJECT
SAW MILLS
NEW MILLS

DRAWING TITLE
FW MANHOLE SCHEDULE

CLIENT
TREVILLE PROPERTIES LIMITED

HBL REF.

8492

DATE

JULY'22

SCALE(S)

1:200

A1

DRAWN

ES

CHECKED

AP

APPROVED

LM

DRAWING No.

8492-HBL-XX-XX-DR-D-0412

REV.

P03