

Pipeline Schedule

Link	Length (m)	Slope (1:X)	Dia (mm)	Link Type	US CL (m)	US IL (m)	US Depth (m)	DS CL (m)	DS IL (m)	DS Depth (m)
1.000	16.427	40.0	150	Circular	150.830	150.380	0.300	150.830	149.969	0.711
1.001	8.699	150.0	150	Circular	150.830	149.969	0.711	150.830	149.911	0.769
1.002	8.887	150.0	150	Circular	150.830	149.911	0.769	150.570	149.852	0.568
1.003	8.652	150.0	150	Circular	150.570	149.852	0.568	150.510	149.794	0.566
1.004	6.629	150.0	150	Circular	150.510	149.794	0.566	150.510	149.750	0.610
1.005	8.189	20.0	150	Circular	150.510	149.750	0.610	150.616	149.341	1.125
1.006	5.314	150.0	225	Circular	150.616	149.341	1.050	150.300	149.306	0.769
1.007	9.154	80.0	225	Circular	150.300	149.306	0.769	149.750	149.192	0.333
1.008	14.296	150.0	225	Circular	149.750	149.192	0.333	149.350	149.097	0.028
1.009	4.362	4.4	225	Circular	149.350	148.150	0.975	149.800	147.160	2.415
2.000	10.495	233.0	150	Circular	150.070	149.470	0.450	150.070	149.425	0.495
2.001	6.306	233.0	150	Circular	150.070	149.425	0.495	150.070	149.398	0.522
2.002	8.511	233.0	150	Circular	150.070	149.398	0.522	150.070	149.361	0.559
2.003	1.094	233.0	150	Circular	150.070	149.361	0.559	150.070	149.356	0.564
2.004	7.507	233.0	150	Circular	150.070	149.356	0.564	150.070	149.324	0.596


Link	US Node	Dia (mm)	Node Type	MH Type	DS Node	Dia (mm)	Node Type	MH Type
1.000	SPPIC1	450	Manhole	Adoptable	SPPIC2	450	Manhole	Adoptable
1.001	SPPIC2	450	Manhole	Adoptable	SPPIC3	450	Manhole	Adoptable
1.002	SPPIC3	450	Manhole	Adoptable	SPPIC4	450	Manhole	Adoptable
1.003	SPPIC4	450	Manhole	Adoptable	SPPIC5	450	Manhole	Adoptable
1.004	SPPIC5	450	Manhole	Adoptable	SPPIC6	450	Manhole	Adoptable
1.005	SPPIC6	450	Manhole	Adoptable	SMH2	1050	Manhole	Adoptable
1.006	SMH2	1050	Manhole	Adoptable	SMH4 HYDRO	1200	Manhole	Adoptable
1.007	SMH4 HYDRO	1200	Manhole	Adoptable	SPPIC23 SWALE START	600	Manhole	Adoptable
1.008	SPPIC23 SWALE START	600	Manhole	Adoptable	SPPIC24	600	Manhole	Adoptable
1.009	SPPIC24	600	Manhole	Adoptable	OUTFALL TO WATERCOURSE	600	Manhole	Adoptable
2.000	SPPIC13	600	Manhole	Adoptable	SPPIC14	600	Manhole	Adoptable
2.001	SPPIC14	600	Manhole	Adoptable	SPPIC15	600	Manhole	Adoptable
2.002	SPPIC15	600	Manhole	Adoptable	SPPIC16	600	Manhole	Adoptable
2.003	SPPIC16	600	Manhole	Adoptable	SPPIC17	600	Manhole	Adoptable
2.004	SPPIC17	600	Manhole	Adoptable	SPPIC18	600	Manhole	Adoptable

Pipeline Schedule

Link	Length (m)	Slope (1:X)	Dia (mm)	Link Type	US CL (m)	US IL (m)	US Depth (m)	DS CL (m)	DS IL (m)	DS Depth (m)
2.005	4.292	233.0	150	Circular	150.070	149.324	0.596	150.300	149.306	0.844
3.000	5.842	117.6	150	Circular	150.350	149.650	0.550	150.570	149.600	0.820
3.001	10.810	117.6	150	Circular	150.570	149.600	0.820	150.570	149.508	0.912
3.002	10.849	117.6	150	Circular	150.570	149.508	0.912	150.570	149.416	1.004
3.003	8.837	117.6	150	Circular	150.570	149.416	1.004	150.616	149.341	1.125
4.000	29.653	250.0	450	Circular	150.330	149.460	0.420	150.616	149.341	0.825
5.000	27.790	150.0	450	Circular	150.800	149.526	0.824	150.616	149.341	0.825
6.000	11.787	80.0	150	Circular	150.070	149.572	0.348	150.070	149.425	0.495
7.000	17.180	100.0	150	Circular	150.180	149.533	0.497	150.070	149.361	0.559
8.000	17.235	100.0	150	Circular	150.180	149.528	0.502	150.070	149.356	0.564
9.000	15.948	100.0	150	Circular	150.830	150.070	0.610	150.830	149.911	0.769
10.000	15.936	100.0	150	Circular	150.830	150.011	0.669	150.570	149.852	0.568
11.000	12.993	100.0	150	Circular	150.510	149.924	0.436	150.510	149.794	0.566

Link	US Node	Dia (mm)	Node Type	MH Type	DS Node	Dia (mm)	Node Type	MH Type
2.005	SPPIC18	600	Manhole	Adoptable	SMH4 HYDRO	1200	Manhole	Adoptable
3.000	SPPIC19	600	Manhole	Adoptable	SPPIC20	600	Manhole	Adoptable
3.001	SPPIC20	600	Manhole	Adoptable	SPPIC21	600	Manhole	Adoptable
3.002	SPPIC21	600	Manhole	Adoptable	SPPIC22	600	Manhole	Adoptable
3.003	SPPIC22	600	Manhole	Adoptable	SMH2	1050	Manhole	Adoptable
4.000	SMH1	1050	Manhole	Adoptable	SMH2	1050	Manhole	Adoptable
5.000	SMH3	1050	Manhole	Adoptable	SMH2	1050	Manhole	Adoptable
6.000	SPPIC12	600	Manhole	Adoptable	SPPIC14	600	Manhole	Adoptable
7.000	SPPIC11	600	Manhole	Adoptable	SPPIC16	600	Manhole	Adoptable
8.000	SPPIC10	600	Manhole	Adoptable	SPPIC17	600	Manhole	Adoptable
9.000	SPPIC7	600	Manhole	Adoptable	SPPIC3	450	Manhole	Adoptable
10.000	SPPIC8	600	Manhole	Adoptable	SPPIC4	450	Manhole	Adoptable
11.000	SPPIC9	600	Manhole	Adoptable	SPPIC5	450	Manhole	Adoptable

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Node Type	MH Type	Connections	Link	IL (m)	Dia (mm)	Link Type	
SPPIC1	402975.115	393538.576	150.830	0.450	450	Manhole	Adoptable		0	1.000	150.380	150	Circular
SPPIC2	402964.669	393525.898	150.830	0.861	450	Manhole	Adoptable		1	1.000	149.969	150	Circular
									0	1.001	149.969	150	Circular
SPPIC3	402957.939	393531.409	150.830	0.919	450	Manhole	Adoptable		1	9.000	149.911	150	Circular
									2	1.001	149.911	150	Circular
									0	1.002	149.911	150	Circular
SPPIC4	402951.063	393537.039	150.570	0.718	450	Manhole	Adoptable		1	10.000	149.852	150	Circular
									2	1.002	149.852	150	Circular
									0	1.003	149.852	150	Circular
SPPIC5	402944.369	393542.520	150.510	0.716	450	Manhole	Adoptable		1	11.000	149.794	150	Circular
									2	1.003	149.794	150	Circular
									0	1.004	149.794	150	Circular
SPPIC6	402939.240	393546.720	150.510	0.760	450	Manhole	Adoptable		1	1.004	149.750	150	Circular
									0	1.005	149.750	150	Circular
SMH1	402912.651	393526.526	150.330	0.870	1050	Manhole	Adoptable		0	4.000	149.460	450	Circular
SMH2	402931.506	393549.413	150.616	1.275	1050	Manhole	Adoptable		1	5.000	149.341	450	Circular
									2	4.000	149.341	450	Circular
									3	3.003	149.341	150	Circular
									4	1.005	149.341	150	Circular
									0	1.006	149.341	225	Circular

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Node Type	MH Type	Connections	Link	IL (m)	Dia (mm)	Link Type	
SMH3	402953.146	393531.978	150.800	1.274	1050	Manhole	Adoptable		0	5.000	149.526	450	Circular
SMH4 HYDRO	402931.212	393554.719	150.300	0.994	1200	Manhole	Adoptable		1	2.005	149.306	150	Circular
									2	1.006	149.306	225	Circular
									0	1.007	149.306	225	Circular
SPPIC23 SWALE START	402925.296	393561.705	149.750	0.558	600	Manhole	Adoptable		1	1.007	149.192	225	Circular
SPPIC24	402914.210	393570.732	149.350	1.200	600	Manhole	Adoptable		0	1.008	149.192	225	Circular
									1	1.008	149.097	225	Circular
									0	1.009	148.150	225	Circular
OUTFALL TO WATERCOURSE	402916.644	393574.352	149.800	2.640	600	Manhole	Adoptable		1	1.009	147.160	225	Circular
SPPIC7	402967.945	393543.828	150.830	0.760	600	Manhole	Adoptable		0	9.000	150.070	150	Circular
SPPIC8	402961.165	393549.364	150.830	0.819	600	Manhole	Adoptable		0	10.000	150.011	150	Circular
SPPIC9	402952.413	393552.724	150.510	0.586	600	Manhole	Adoptable		0	11.000	149.924	150	Circular

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Node Type	MH Type	Connections	Link	IL (m)	Dia (mm)	Link Type	
SPPIC10	402910.424	393556.398	150.180	0.652	600	Manhole	Adoptable		0	8.000	149.528	150	Circular
SPPIC11	402909.780	393555.512	150.180	0.647	600	Manhole	Adoptable		0	7.000	149.533	150	Circular
SPPIC12	402904.659	393540.713	150.070	0.498	600	Manhole	Adoptable		0	6.000	149.572	150	Circular
SPPIC13	402907.120	393525.069	150.070	0.600	600	Manhole	Adoptable		0	2.000	149.470	150	Circular
SPPIC14	402913.747	393533.207	150.070	0.645	600	Manhole	Adoptable		1 2	6.000 2.000	149.425 149.425	150 150	Circular Circular
SPPIC15	402917.749	393538.080	150.070	0.672	600	Manhole	Adoptable		1 0	2.001 2.002	149.398 149.398	150 150	Circular Circular
SPPIC16	402923.118	393544.684	150.070	0.709	600	Manhole	Adoptable		1 2 0	7.000 2.002 2.003	149.361 149.361 149.361	150 150 150	Circular Circular Circular
SPPIC17	402923.805	393545.535	150.070	0.714	600	Manhole	Adoptable		1 2 0	8.000 2.003 2.004	149.356 149.356 149.356	150 150 150	Circular Circular Circular

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Node Type	MH Type	Connections	Link	IL (m)	Dia (mm)	Link Type	
SPPIC18	402928.538	393551.362	150.070	0.746	600	Manhole	Adoptable		1	2.004	149.324	150	Circular
									0	2.005	149.324	150	Circular
SPPIC19	402929.218	393520.910	150.350	0.700	600	Manhole	Adoptable		0	3.000	149.650	150	Circular
SPPIC20	402932.931	393525.420	150.570	0.970	600	Manhole	Adoptable		1	3.000	149.600	150	Circular
									0	3.001	149.600	150	Circular
SPPIC21	402924.587	393532.292	150.570	1.062	600	Manhole	Adoptable		1	3.001	149.508	150	Circular
									0	3.002	149.508	150	Circular
SPPIC22	402931.592	393540.576	150.570	1.154	600	Manhole	Adoptable		1	3.002	149.416	150	Circular
									0	3.003	149.416	150	Circular