


GENERAL NOTES

1. NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS ALLOWED WITHOUT PRIOR PERMISSION IN WRITING.
2. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL ARCHITECTS, ENGINEERS AND SPECIALISTS DRAWINGS AND THE SPECIFICATION.
3. THE CONTRACTOR SHALL INCORPORATE ALL THE REQUIREMENTS OF THE PRE-TENDER STAGE HEALTH AND SAFETY PLAN.

KEY

- RED LINE BOUNDARY
- AXLE PATH OF VEHICLE
- SWEEP BODY OF VEHICLE
- AXLE PATH OF VEHICLE - REVERSE
- SWEEP BODY OF VEHICLE - REVERSE



Refuse 2 Drop Recycler (P2 15W with Elite 6x4 chassis)
Overall length 11.220m
Overall width 2.550m
Overall body height 3.500m
Min body ground clearance 0.500m
Front wheel 2.500m
Rear wheel 2.500m
Kerb to kerb turning radius 11.000m

PRELIMINARY

P03	ISSUED FOR PLANNING APPROVAL	14.04.26	DB	AL
P02	REVISED TO SUIT UPDATED SITE LAYOUT	11.03.26	DB	AL
P01	PRELIMINARY ISSUE	08.08.25	DB	AL
Rev.	Amendment	Date	By	Chkd

Project
MIRY MEADOW

ARCHITECT
MELLOR HOMES

Title
VEHICLE TRACKING
REFUSE VEHICLES

WML Job No	Drawn	Checked	Date	Scale
10766	AS	MS	08.08.25	1:200 @ A0

WML CONSULTING
Civil, Structural & Geotechnical Engineers
Third Floor South
Metropolitan House
Station Road
Chesham HP8 7JZ
Tel: 0161 482 5000
Fax: 0161 482 5010
e-mail: info@wmlconsulting.com
www.wmlconsulting.com

Drawing No.	Project	Originator	Volume	Level	Type	Role	Number	Rev
10766	WML	ZZ	ZZ	DR	C	-	0101	P03

